

Brookfield Resource Management Inbound Materials Inspection Protocol

1. Signage shall be placed at the entrance of the facility outlining materials that are acceptable.
2. Signage shall be placed at the entrance of the facility outlining materials that will not be accepted, including; municipal solid waste, municipal stream recyclables, hazardous waste, radioactive materials or medical waste.
3. Once on the scale, the scale operator will inspect the load via cameras and visually through the scale house window.
4. If loads are leaking petrochemicals, the load will be isolated and the spill cleaned up using absorbent materials before the load may proceed into the site proper. A spill kit will be maintained at the scale house at all times, and the staff trained to assure compliance with prevailing regulations.
5. While on the scale the loads are scanned for radioactive materials.
6. At the unloading area the operator will visually inspect all material being unloaded.
7. Once on the ground the operator will look over the material one last time prior to releasing the trucker.
8. Material is subject to random inspections throughout operating hours by management.
9. Rejected loads that, in the opinion of the operators, represent a hazard to the general health, safety and welfare of the community shall be reported to the appropriate authorities.